

3.02 Erection:

A. Drawings

Erect panels plumb, level, and square in strict accordance with the approved shop drawings.

B. Handling And Lifting

Handling and lifting the precast panels shall be done in such a manner as to not cause significant distortion.

C. Panels

Panels shall be plumbed, aligned and securely attached to the supporting structures in accordance with approved erection drawings.

D. Bracing

Temporary bracing shall be provided if necessary until erection is complete.

E. Vertical Movement

Provision for vertical movement shall be provided where indicated on the approved erection drawings in accordance with Engineered Wall Corp., recommendation.